

BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

NEGOTIATED SCHEDULE - B

Improvements to roads and drains at Hegdenagara and surrounding Areas in Ward No.06

SNo	Quantity	Item Name	Unit	Negotiated Rates quoted by K S CHOWDAREDDY	
				In figures	In words
1	2282.46	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)	Cum	226.04	Rupees Two Hundred Twenty Six And Paise Four Only
2	335.61	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222, I No-27.18)	Cum	5693.00	Rupees Five Thousand Six Hundred Ninety Three Only
3	694.43	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete excluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWD S.R 2018-19)	Cum	7423.71	Rupees Seven Thousand Four Hundred Twenty Three And Paise Seventy One Only
4	50.36	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWD S.R 2018-19)	MT	77691.85	Rupees Seventy Seven Thousand Six Hundred Ninety One And Paise Eighty Five Only
5	1631.79	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	2453.85	Rupees Two Thousand Four Hundred Fifty Three And Paise Eighty Five Only
6	149.31	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete, 10 cms thick. Page No. 27/ Item No. 5.31.2 PWD SR 2018-19	Sqm	1015.06	Rupees One Thousand Fifteen And Paise Six Only

K.S. Chowdareddy
Contractor

Quantity	Item Name	Unit	Negotiated Rates quoted by K S CHOWDAREDDY	
			In figures	In words
149.31	Providing One line dressing to granite stone slab/ granite stone masonry as per specification (P.No.26, I.No.5.17 of PW,P&IWTDR SR 2018-19)	Sqm	998.36	Rupees Nine Hundred Ninety Eight And Paise Thirty Six Only
8 97.50	Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	5688.90	Rupees Five Thousand Six Hundred Eighty Eight And Paise Ninety Only
9 49.56	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No.4.6 of PW, P&IWTDR SR 2018-19)	Cum	6034.69	Rupees Six Thousand Thirty Four And Paise Sixty Nine Only
10 3671.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTDR SR 2018-19)	Nos	454.10	Rupees Four Hundred Fifty Four And Paise Ten Only
11 660.80	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWTDR SR 2018-19)	Sqm	89.04	Rupees Eighty Nine And Paise Four Only